

Essen Grugapark, Germany

The Project:

New construction of Essen Grugapark, Germany
Executing Company: Hochtief Building
Equipment provided by Streif Baulogistik

The Problem:

The ground water and collected surface water must be pumped off.

Our Solution:

The water is pumped off via a 200m long hose line by a KTZ45.5 which is installed horizontally for space reasons.
Sufficient capacity reserves are available even in case of heavy rainfall.



Προδιαγραφές KTZ: <https://www.tsurumi.eu/el-CY/ktz>

Σε περίπτωση χρήσης λειαντικού ή διαβρωτικού μέσου, μπορεί να προκληθεί μεγάλη φθορά σε ορισμένα εξαρτήματα. Αναφορικά με την παραπάνω εφαρμογή, μπορεί να προκληθεί φθορά κυρίως στην πτερωτή, στον αναδευτήρα, στην πλάκα αναρρόφησης, στο χιτώνιο ολίσθησης του άξονα, στον δακτύλιο λίπανσης, στο μηχανικό στεγανωτικό παρέμβυσμα, στο περιβλήμα της αντλίας, στο φίλτρο, στο κιβώτιο του κινητήρα και στον άξονα σύζευξης του συστήματος αποστράγγισης. Η διάρκεια ζωής αυτών των εξαρτημάτων μπορεί να διαφέρει σημαντικά και μπορεί να είναι συντομότερη από εκείνη της περιόδου της εγγύησης κατά τον νόμο, εξαρτάται από τις συνθήκες εργασίας.

Όσον αφορά αυτό θα πρέπει να δοθεί προσοχή στους γενικούς όρους και κανονισμούς που σας έχουμε επίσης στείλει μέσω ταχυδρομείου κατόπιν αιτήματος.

