

Essen Grugapark, Germany

The Project:

New construction of Essen Grugapark, Germany
Executing Company: Hochtief Building
Equipment provided by Streif Baulegistik

The Problem:

The ground water and collected surface water must be pumped off.

Our Solution:

The water is pumped off via a 200m long hose line by a KTZ45.5 which is installed horizontally for space reasons.
Sufficient capacity reserves are available even in case of heavy rainfall.



Špecifikácie KTZ: <https://www.tsurumi.eu/sk-SK/ktz>

V prípade použitia v abrazívnom alebo korozívnom prostredí sa niektoré súčasti prirodzene opotrebojú rýchlejšie. S ohľadom na takúto aplikáciu sa opotrebenie môže týkať hlavne obežného kolesa, miešadla, sacej dosky, puzdra hriadeľa, olejového tesnenia, mechanického tesnenia, krytu čerpadla, sita, krtyu motora a spojky odtoku. V závislosti od pracovných podmienok sa životnosť týchto súčastí môže podstatne líšiť a byť kratšia než zákonná záručná doba.

Preto, prosím, vezmite do úvahy naše [všeobecné zmluvné podmienky](#), ktoré vám na vyžiadanie zašleme poštou.

